

ANGÉLICA INFANTE-GREEN
Commissioner

DR. JAVIER MONTAÑEZ
Interim Superintendent



Providence Public School District
Purchasing Department
797 Westminster Street
Providence, RI 02903-4045
tel. 401.456.9264
fax 401. 456.9252
www.providenceschools.org

Addendum #1

Safety Netting at Classical High School

Issue Date: Monday, July 12, 2021

Bids Due: Wednesday, July 21, 2021 at 1PM

Replace Bid Form 2 (page 7 of the solicitation) with the Revised Bid Form 2 found on page 2 of this document (Addendum #1).

1. Can excavated spoils be left piled on site, hauled to a spot on site and dumped, hauled to another PPSD location to be dumped, or hauled away and disposed of by the contractor?

Excavated spoils will be hauled by the contractor to a site of PPSD's choice (likely Mt. Pleasant High School / Conley Stadium).

2. Any tree trimming work will be the responsibility of PPSD or the contractor?

Tree trimming work will be the responsibility of the City of Providence Parks Department.

3. Can we use a lull (lifting equipment) on the artificial turf field?

No equipment can be used on the artificial turf field.

REVISED BID FORM 2: PRICING

Item	Cost
<p>OUTDOOR FIELD NETTING SYSTEM</p> <ul style="list-style-type: none"> • Custom Pole-to-Pole Tension Ball Safety Netting System, including “Super Durable” Powder-Coated Steel Poles, Cabline, Hardware Per Drawings and Specifications, and Black Ultra Cross ® Knotless Dyneema ® Netting with 1 ¾” square mesh • 180’ (60 yards) of netting • 15”H Ultra Cross Netting overtop 8’H IRF (23’H Overall), including (10) 6.625 x 0.280 steel poles that are 27”L for a 4’ Embedment • Steel Ground Sleeve for 6” Post – 7.000”OD x 48L, including stop-bolt and leveling plate 	
<p>Football Goal Post Pads</p> <ul style="list-style-type: none"> • Ten (10) Hexagonal pads with digitally-printed lettering/graphics (graphics to be provided following award) 	
<p>Installation</p> <ul style="list-style-type: none"> • Sleeves to be set in 3500psi concrete bases with minimum depth of 48” and minimum diameter of 48” • Posts, netting and hardware to be installed per manufacturer’s specifications 	
Total Cost	